BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2014-15/OW/WORK_INDENT17193

APPROVED SCHEDULE - B

EE/BTP BMP/E-PMT/10/2014-15, Date: 21.02.2015

Maintenance of BBMP Drilling Borewells in Kodigehalli ward no. 08 Kodigehalli sub division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of LAKSHMINARAYAN V	
				In Figures	In Words
1	30	Lifting of Submersible pump set as per Soecification and direction etc complete as per specifications and directions of engineer in charge of the work	Each	841.50	Rupees Eight Hundred Forty One and Fifty Paise Only
2	30	Transportation of pumping machineries etc complete as per specifications and directions of engineer in charge of the work	Each	891.00	Rupees Eight Hundred Ninety One Only
3	30	Labour charges (over hauling) etc complete as per specifications and directions of engineer in charge of the work	Job	544.50	Rupees Five Hundred Forty Four and Fifty Paise Only
4	10	A) Repairs to Motor: Rewinding of submersible pump sets with copper insulation wire of suitable gauge as per ISI specification with guarantee of 6 months. (Above 10 HP upto 20 HP add Rs.150/- for every ◆ HP) up to 10 HP etc complete as per specifications and directions of engineer in charge of the work 10.00 HP	No.	3663.00	Rupees Three Thousand Six Hundred Sixty Three Only
5	20	12.5 HP	No.	4702.50	Rupees Four Thousand Seven Hundred Two and Fifty Paise Only
6	30	Starter (with one year Guarantee) etc complete as per specifications and directions of engineer in charge of the work	No.	4999.50	Rupees Four Thousand Nine Hundred Ninety Nine and Fifty Paise Only
7	30	Rotor (with one year Guarantee) etc complete as per specifications and directions of engineer in charge of the work	No.	4653.00	Rupees Four Thousand Six Hundred Fifty Three Only
8	30	Upper Flange etc complete as per specifications and directions of engineer in charge of the work	No.	346.50	Rupees Three Hundred Forty Six and Fifty Paise Only
9	30	Lower Housing etc complete as per specifications and directions of engineer in charge of the work	No.	643.50	Rupees Six Hundred Forty Three and Fifty Paise Only
10	30	Carbon Housing etc complete as per specifications and directions of engineer in charge of the work	No.	470.25	Rupees Four Hundred Seventy and Twenty Five Paise Only
11	30	Thrust bearing block assembly complete with Segment bearing pad etc complete as per specifications and directions of engineer in charge of the work	No.	1138.50	Rupees One Thousand One Hundred Thirty Eight and Fifty Paise Only
12	30	Oil Seal etc complete as per specifications and directions of engineer in charge of the work	No.	123.75	Rupees One Hundred Twenty Three and Seventy Five Paise Only
13	30	Oil Seal Steel Bush etc complete as per specifications and directions of engineer in charge of the work	No.	148.50	Rupees One Hundred Forty Eight and Fifty Paise Only
14	450	Guide vane etc complete as per specifications and directions of engineer in charge of the work	No.	173.25	Rupees One Hundred Seventy Three and Twenty Five Paise Only
15	450	Impeller Shell moulded with aluminium Bronze) etc complete as per specifications and directions of engineer in charge of the work	No.	420.75	Rupees Four Hundred Twenty and Seventy Five Paise Only

16	30	Discharge outlet (D.O) Bearing D.O Steel Bush etc complete as per specifications and directions of engineer in charge of the work	No.	440.55	Rupees Four Hundred Forty and Fifty Five Paise Only
17		Steel Bush etc complete as per specifications and directions of engineer in charge of the work	No.	148.50	Rupees One Hundred Forty Eight and Fifty Paise Only
18	30	Pump shaft made out of stainless steel Centreless ground with key way (upto 8 stages) etc complete as per specifications and directions of engineer in charge of the work	No.	940.50	Rupees Nine Hundred Forty and Fifty Paise Only
19	30	Non – return valve (NRV) assembly complete with rubber 'O' Ring etc complete as per specifications and directions of engineer in charge of the work	No.	1336.50	Rupees One Thousand Three Hundred Thirty Six and Fifty Paise Only
20	30	Cable Guard etc complete as per specifications and directions of engineer in charge of the work	No.	148.50	Rupees One Hundred Forty Eight and Fifty Paise Only
21	30	Brass Filter etc complete as per specifications and directions of engineer in charge of the work	No.	247.50	Rupees Two Hundred Forty Seven and Fifty Paise Only
22	30	Re-erection charges of pumping machineries including overhauling and pointing etc complete as per specifications and directions of engineer in charge of the work	Each	940.50	Rupees Nine Hundred Forty and Fifty Paise Only
23	145	Supplying and drawing 3 core flat PVC sheathed submersible pump cable manufactured with electrolytic grade copper with flexible copper conductor confirming to table 3 class 5 of IS:8130-1984 and virgin grade PVC insulation and sheathed suitable for working voltage upto 1100 Volts. P. No. 49/ I No. 29-b(1) 4 Sqm mm of 56 strands 0.3mm dia Group - A etc complete as per specifications and directions of engineer in charge of the work	Mtr	149.49	Rupees One Hundred Forty Nine and Forty Nine Paise Only

J. Narayan. V

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92